BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: EE/RRND/Tend/11/2020-21 Date: 20.02.2021

Indet No: BBMP/2020-21/RD/WORK_INDENT46975

SCHEDULE -B

Name of Work: Comprehensive development of Roads and Drains in near KK Apartments and Pipeline road surrounding areas in ward no 16 Jalahalli

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	1067.04	Removing and refixing stone slabs of drains and pointing in CM (1:3) Complete as per the Direction of Engineer-in-charge.	Sqm	102.12	Rupees One Hundred Two And Paise Twelve Only
2	321.84	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods Complete as per the Direction of Engineer-in-charge.	Cum	213.96	Rupees Two Hundred Thirteen And Paise Ninety Six Only
3	447.12	Providing & laying precast drain cover slab of 100 mm thickness in CM 1:3 including cost of all materials, labour, curing, transportation, loading, unloading etc, complete as per the directions of the Engineer In Charge.(0.90 x 0.60 x 0.10) Complete as per the Direction of Engineer-in-charge.	Sqm	2144.20	Rupees Two Thousand One Hundred Forty Four And Paise Twenty Only
4	5.00	Providing & laying precast drain cover slab of 250 mm thickness in CM 1:3 including cost of all materials, labour, curing, transportation, loading, unloading etc, complete as per the directions of the Engineer In Charge.(1.20 x 0.60 x 0.25) Complete as per the Direction of Engineer-in-charge.	Sqm	4971.02	Rupees Four Thousand Nine Hundred Seventy One And Paise Two Only
5	736.00	Providing and fixing pre cast solid concrete kerb stones of size 450x150x500 mm made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting ete., Complete as per the Direction of Engineer-in-charge.	nos	428.89	Rupees Four Hundred Twenty Eight And Paise Eighty Nine Only
6	496.80	Providing and applying spray painting (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. Complete as per the Direction of Engineer-in-charge.	Sqm	53.49	Rupees Fifty Three And Paise Forty Nine Only
7	496.80	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.	Sqm	77.80	Rupees Seventy Seven And Paise Eighty Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP